

9.0 Required Notes on Design Plans

1. This system (is / is not) designed for the use of a garbage disposal.
2. This system is not designed for backwash from a water softener.
3. On raised systems, the organic loam layer must be removed from trench or bed and slope extension areas prior to fill placement. A bucket with teeth is best used for this construction step as buckets without teeth can compact and smear the underlying soil.
4. Scarify subsoil prior to fill placement.
5. Backfill material shall meet Section 11(E) Table 11A of the Maine Rules. All backfill material shall be clean bank run sand, free of topsoil or humus and dredging directly beneath the EDA.
6. The 6" underneath and 9" surrounding the GSF modules shall be installed using a medium to coarse washed sand with an effective size of 0.25 to 2.0 mm, no greater than 10% passing a #100 sieve and no greater than 5% passing a #200 sieve, and no particles larger than .375", or materials meeting the ASTM C33 specification with less than 10% passing a #100 sieve and less than 5% passing a #200 sieve. Washed concrete sand easily meets the above specification and is a reliable choice. Suitability of bank run sand must be verified.
7. Fill (cover material) and Backfill material (fill added below and around the GSF Specified Sand envelope) shall be bank run sand with less than 4 to 8% passing a #200 sieve and clay less than 2% and no stones larger than 3" in any dimension to a minimum depth of 12" over the GSF modules with the last 4" to 6" of cover being clean loam.
8. Any system which is more than 18" below finish grade as measured from the top of the modules shall be vented.
9. This design complies with and must be installed in accordance with the Eljen Design and Installation Manual.